
NSLS II Town Meeting

February 27, 2018

Safety Update

- Injuries
- Configuration Control
- EEI




Configuration Control

Scarify Event; Tunnel Roof Shielding

- SCBNL; "Scarifying concrete on tunnel roof reduces required radiological shielding"
- February 16, 2018 (notification)
- ~25 millimeters of concrete removed


Authorization basis

- Accelerator Safety Envelope (ASE)
 - Credited controls
 - Shielding; PPS; burn throughs, TOSS, electron charge & energy limits, operator coverage, hutch O2 sensors
 - Un-reviewed Safety Issue (USI)



Configuration Control; Radiation Safety Components

- Radiation Safety Components
 - shutters, scatter shields, burn through devices, labyrinths, beam stops, beam masks, PPS apertures, collimators, guillotines, transport pipe, berms, beamline enclosures, accelerator enclosures, area radiation monitors.
- Systems for configuration control:
 - Component labeling and checklists
 - Personnel Protection system (PPS)





U.S. DEPARTMENT OF ENERGY







User Labyrinth

Configuration
Control Labeling





Safety System Work Permits Change Control – Return to Service

- Tool to support and document the process
- Four page form
 - White copy
 - Posted at site
 - Yellow copy
 - In Control Room
 - Blue copy
 - On white board
 - Pink copy
 - RCD (rad survey)
- Sections
 - Work description
 - Controls; <u>USI</u>
 - Return to service requirements
 - Approve/Post/Close
 - Feedback



Safety System Work Permit

To be completed by person requesting the permit	
Today's date: Estimated start date:	Estimated end date:
Description of work:	
Personnel performing work:	
Configuration Control □ Shielding □ RSC □ Other	PPS Configuration Control □
Controls:	Controls:
USI: ☐ Exempt ☐ Non-Exempt (ABM Signature Req'd)	USI: ☐ Exempt ☐ Non-Exempt (ABM Signature Req'd)
□ Lock Out & Yellow Tag:	□ Lock Out & Yellow Tag:
☐ Lock Out Tag Out:	□ Lock Out Tag Out:
□ Other:	Other:
Lockouts placed by: Date:	Lockouts placed by: Date:
Return to service requirements:	Return to service requirements:
☐ New installation traveler required	☐ Full test:
☐ FLOCO / Operator inspection	☐ Partial test:
☐ Safety staff inspection	☐ Functional test:
☐ Other:	
	Other:
☐ Radiation survey conditions:	Approved by: Date:
Approved by: Date:	Released by: Date:
Released by: Date:	
Return to service; Date:	
Rad survey by: Date:	
Posted by: Date:	TI: D 1: C C-1
	This Radiation Safety
Permit closed by: Date:	
LF3164F (rev. 10/15) WHITE copy to be posted at work site, wh	Component Currently
	Component Currently
	IOTIL 1 C . C
	VOT Under Configuration
	Managament
	Management

Electrical Equipment Inspections (EEI)

Electrical Equipment Inspection

- New program; emphasis and resources assigned
- Nationally Recognized Testing Laboratory



- No NRTL; Need more time for inspection
- EEI Guide
 - Need documentation
 - Commercial Off the Shelf (COTS) User
 Manual
 - Built in House (BIH) schematic, block diagram, wiring, parts list, ...
 - Shock isolation
 - External cabling
 - Overcurrent protection
 - Foreign (non-US) power supplies
 - Checklist for Non-NRTL

ELECTRICAL EQUIPMENT INSPECTION (EEI) CRITERIA GUIDE

SCOPE

To meet the Department of Energy's Electrical safety guidelines, DOE-HDK-1092-2013 (https://www.standards.doe.gov/standardsdocuments/1000/1092-BHdbk-2013/@@images/file), it is strongly encouraged that all equipment (chassis, cables, etc.) containing voltages above 50 volts be approved by a Nationally Recognized Testing Lab (NRTL) certified units.

(https://www.osha.gov/dts/otpca/nrti/nrtllist.html) However, BNL recognizes that not every experimental installation can use solely NRTL systems in performing an experiment. This condensed guide is intended for the beam line user community on what are the minimum electrical safety concerns when low voltage (less than 50 V) designs are impossible and a "one off" custom design must be fabricated and brought to the NSLS-II for an experiment to be performed.

Documentation is required for devices not NRTL certified. This documentation is required to ensure a proper safety review and a correct implementation of the device. For Commercial Off The Shelf (COTS) devices not NRTL certified the manufacturer's user manual can suffice as this documentation. For Built In House (BIH) custom devices the schematic, block diagram, whiring, parts list and any other documentation used to build the custom device should be made available to an inspector well in advance of planned use to avoid any delays. Any custom cabling (except mains power connection) containing over 50V outside of the chassis must be identified.

Preventing personnel from a shock and preventing a fire due to overcurrent conditions are the two primary safety concerns to any electrical design.

ALL DEVICES NOT NRTL CERTIFIED WILL REQUIRE MORE INSPECTION TIME THAN NRTL DEVICES. BIH DEVICES WILL
REQUIRE MORE INSPECTION TIME THAN COTS DEVICES. DOCUMENTATION SUBMISSION WELL IN ADVANCE OF
SCHEDILLED OPERATION. CAN EXPEDITE THE INSPECTION TIME.

PERSONNEL ISOLATION FROM SHOCKS

People are <u>not</u> permitted to touch an exposed conductor energized above 50 V RMS from ground potential, even accidentally.

Naturally every chassis must be undamaged and not provide access to any energized conductor without the use of a tool. There are
two approved methods in the electrical industry to assure personnel isolation; grounded/bonded and double insulated chassis
designs.

GROUNDED/BONDED CHASSIS

This is the <u>preferred</u> technique for any ground referenced voltages above 50 V RMS (e.g., mains supply) in a chassis. The outer conductive chassis acts as a safety barrier between personnel and dangerous voltages by itself being bonded to ground. All mains power provides a ground connection that must be connected directly to the chassis. Painted surfaces at the point of contact must be scraped clean to provide a solid connection to ground. When the contained voltages exceed 600 V an additional external bonding point should be added to the chassis for a secondary bond path.

DOUBLE INSULATED CHASSIS





NRTLs - Certification Marks




























Is NOT an NRTL Mark





